NATIONAL AGRI-FOOD BIOTECHNOLOGY INSTITUTE, MOHALI

DEPARTMENT OF BIOTECHNOLOGY
(Govt. of India)

1.0	General Information
	NABI

Q U O T A T I O N   D O C U M E N T S

(General Information)

Name of Work: SCHEDULE OF QUANTITIES FOR PROVIDING AND FIXING MID HEIGHT TOUGHENED GLASS CABINS NEAR CONFERENCE ROOM AT GROUND FLOOR, INTERIM FACILITY, NABI

Estimated Cost: Rs 87486/- (Rupees Eighty Seven Thousand Four Hundred Eighty Six only)

Completion Period: 4 weeks

Last Date of submission of Quotation: Ist July 2013 up to 3.00 pm

Date of Opening of Quotation : Ist July 2013 at 3.30pm

(In the office of Assistant Engineer (Civil), NABI, Mohali)

SCHEDULE OF QUANTITIES FOR PROVIDING AND FIXING MID HEIGHT TOUGHENED GLASS CABINS NEAR CONFERENCE ROOM AT GROUND FLOOR ,INTERIM FACILITY, NABI

S. No	Description of Item	Unit	Quantity	Rate (In Figures)	Rate (In Words)	Amount
1.	Providing and fixing mid height glass partition with 12mm toughened glass (new glass) including silicon filling wherever required (including labour charges etc)	Sft	117.00			
2.	Fixing(labour) charges for existing glass available at site	sft	81.00			
3.	Supplying and fixing of wall connecting profile (wcp) for fixing of toughened glass including making holes and cost of fixing screws as required.	metre	28			
4.	Labour charges for fixing existing SS pillars for supporting toughened glass including cutting tiles and making good the surface with matching tiles.	each	6			
	Total Amount (In Words & Figures) inclusive of all taxes, profits & overheads etc.					

Terms & Conditions:-

1.   The Work shall be as per CPWD specifications Vol-I & II 2009.
2.   Rates quoted should be inclusive of all taxes, labour charges, Profit etc.
3.   Conditional/Incomplete quotations shall be rejected.
4.   Statutory tax deductions, if any as per rules of Govt. shall be deducted.

Signatures & Stamp of Contractor